BRUHATH BANGALORE MAHANAGARA PALIKE, DASARAHALLI ZONE

Office of the Executive Engineer Dasarahalli Division,

SCHEDULE-B

Name of Work: Reserve fund for emergency work in Bagalagunte in ward no.14 (Drilling of bore well at soap factory layout & Royal enclave, Providing pump motor & servicing)

Sl.No	Description of work	Unit	Qty	Sanctioned Approved Rates	
				In Figures	In Words (Rs.)
1	2	3	4	5	6
1	Geophysical investigation of site for sinking borewell for supplying drinking water to the habitation either through the hand pump, MWS or P.W.S.S. by vertical electrical sounding by adopting venner or schlumbergers's method, including reconnaissance survey of geological formation, Geological investigation of existing ground water in vicinity, its quality, quantity & acceptability of the users indicating the location of site, recommended depth of casing pipe required to seal the top unconsolidated formation including an extra depth of 1.0 mtr in consolidated formation for proper seating of casing pipe, depth of drilling required to cover full depth of aquifer proposed to be tapped, probable yield and other information required including transportation of instrument and accessories to work site, engaging technical personal and labour required etc Complete as per Specification.	each	2.00	1900.00	Rupees One Thousand Nine Hundred Only
2	Sinking of borewell of 165 mm dia clear using super fast hydraulic rig of capacity 250 PSIG & above 900 CMF & above in all strata including over budern upto 20 m. fixing of casing pipes, collars & cap with necessary cutting, threading & welding including transportation of rig and supporting vehicle, crew charges & cost of consumables etc., complete including yield testing at the final depth with minimum working of compressor for one hour(excluding cost of casing pipes, collars, cap etc.,) Complete as per Specification.				
a	0.00 to 50.00 Mtr.	Mtr	100.00	306.00	Rupees Three Hundred Six Only
b	50.00 to 100.00 Mtr.	Mtr	100.00	400.00	Rupees Four Hundred Only
c	100.00 to 150.00 Mtr.	Mtr	100.00	445.00	Rupees Four Hundred Forty Five Only
d	150.00 to 200.00 Mtr.	Mtr	100.00	470.00	Rupees Four Hundred Seventy Only
e	200.00 to 250.00 Mtr.	Mtr	100.00	544.00	Rupees Five Hundred Fort Four Only

Executive Engineer

Signature of the Contractor

EXECUTIVE ENGINEER